

## APPENDIX D: FURNITURE, FIXTURES AND EQUIPMENT REQUIREMENTS

### ITEMIZED FURNITURE, FIXTURES & EQUIPMENT (FF&E) REQUIREMENTS

**LEGEND:**

<b>CFCI:</b>	Contractor Furnished, Contractor Installed Items
<b>GFCI:</b>	Government Furnished, Contractor Installed Items
<b>GFGI:</b>	Government Furnished, Government Installed Items

**General Notes:**

- A. Refer to RFP Specification Section 01158/1.17 for specific Performance Criteria of each item. Each item is referenced per Spec Code in the RFP Specifications.
- B. GFGI & GFCI Items: Contractor is responsible to confirm, coordinate, provide and install all necessary building infrastructure and features, such as, but not limited to HVAC, electrical power, telecommunications connectivity, spatial and clearance requirements for all items to ensure each item is operational and maintainable in accordance with USCG requirements.
- C. Photo Images provided are for reference only; coordination of requirements shall be confirmed and approved with the USCG representative during design phase services. Reference imagery is not provided for all items; It is the Contractor's responsibility to confirm and coordinate as necessary for a complete installation.
- D. SF & Extended SF amounts identified in Appendix 'D' are already included in the minimum net area of each room provided in the Space Criteria Sheets. SF is only intended as reference for FFE layout purposes.
- E. See Space Criteria Sheets for whiteboard, walk-off mat, and other items required.

LINE NO.	SPEC CODES	RESPONSIBILITY	QTY	DESCRIPTION	SF	Extended SF	REMARKS	
<b>Station Engineering, Room 104</b>								
1	C1	CFCI	4	Ergonomic Desk Chair		---	nominal dimensions, may vary with layout	
2	C3	CFCI	3	Guest Side Chair	10	30		
3	CL1	CFCI	1	Wall Clock				
4	F1	CFCI	1	File Cabinet, 4 dwr high (shared)	10.5	11		
5	S1	CFCI	3	Bookshelf (Shared Reference Manuals)	9	27		
6	S2	CFCI	2	Storage Cabinet, Full height, interior shelves; shared storage	36	72		
7	W1	CFCI	1	Tall Waste Basket				
8	W2	CFCI	4	Metal Waste Basket				
9	WS1	CFCI	3	Workstation	36	108		See Specifications for component & performance criteria
10	WS2	CFCI	1	Shared, Touch-down WorkStation	25	25		See Specifications for component & performance criteria
11	X8	GFGI	0	(4) computers, (3) printers, (0) shredder	0	0		Coordinate connectivity and power requirements with Section 01158 Electrical
<b>SUBTOTALS:</b>						<b>273</b>		
<b>Minimum SF Requirements (with Circulation @ 31%):</b>						<b>357</b>		
<b>Maintenance/Snow Removal, Room 113</b>								
12	R36	CFCI	3	Racks: adjustable shelving	15	45		
13	TS1	CFCI	2	Wall Mounted, Tool and Broom racks/holders; rubber coated	0	0		
14	W1	CFCI	1	Tall Waste Basket				
14	XSP	GFGI	1	Storage Platform	36	36		
<b>SUBTOTALS:</b>						<b>81</b>		
<b>Minimum SF Requirements (with Circulation @ 40%):</b>						<b>113</b>		

E. See Space Criteria Sheets for whiteboard, walk-off mat, and other items required.

LINE NO.	SPEC CODES	RESPONSIBILITY	QTY	DESCRIPTION	SF	Extended SF	REMARKS
<b>Boatswain Maintenance (BM) Shop/Storage, Room 105</b>					<b>SF</b>	<b>Extended SF</b>	
15	C2	CFCI	1	Shop Work Stool, casters and ring base	0	0	
16	CL1	CFCI	1	Wall Clock			
17	R30	CFCI	4	Racks: adjustable shelving	14	56	
18	TS2	CFCI	1	5-Dwr Tool Storage Unit,	27	27	mobile tool storage units
19	TS3	CFCI	2	10-Dwr Tool Storage Unit	27	54	mobile tool storage units
20	W1	CFCI	1	Tall Waste Basket			
21	WB1	CFCI	2	Workbench, hardwood top	27	54	No integral power provided
22	XC1	GFCI	2	Rope & Reel Stands (one L-shaped w/ fixed shelves)	25	50	
23	XC2	GFCI	1	Table Vice	0	0	Remove and relocate from Existing WorkBench & Install
24	XC3	GFCI	5	Tool Storage Units (Vidmars)			
25	XC4	GFCI	1	Racks: adjustable shelving; Verify dimensions			
<b>SUBTOTALS:</b>						<b>241</b>	
<b>Minimum SF Requirements (with Circulation @ 31%):</b>						<b>316</b>	
<b>RS &amp; S Storage, Room 107</b>					<b>SF</b>	<b>Extended SF</b>	
26	C2	CFCI	1	Shop Work Stool, casters and ring base	0	0	
27	R30	CFCI	2	Racks: adjustable shelving	14	28	
28	TS3	CFCI	2	10-Dwr Tool Storage Unit	27	54	mobile tool storage units
29	WB1	CFCI	1	Workbench, hardwood top	27	27	
<b>SUBTOTALS:</b>						<b>109</b>	
<b>Minimum SF Requirements (with Circulation @ 31%):</b>						<b>143</b>	
<b>Cutter Neah Bay Shop /Storage, Room 119</b>					<b>SF</b>	<b>Extended SF</b>	
30	C2	CFCI	2	Shop Work Stool, casters and ring base	0	0	
31	FS1	CFCI	3	Flammable liquids storage cabinets	12	36	
32	R36	CFCI	11	Racks: adjustable shelving	15	165	
33	SS1	CFCI	15	Welded Wire Bulk Storage	15	225	
34	TS2	CFCI	2	5-Dwr Tool Storage Unit, (under workbench)	0	0	mobile
35	TS3	CFCI	2	10-Dwr Tool Storage Unit	27	54	mobile tool storage units
36	W1	CFCI	1	Tall Waste Basket			
37	WB1	CFCI	4	Workbench, hardwood top	27	108	
<b>SUBTOTALS:</b>						<b>588</b>	
<b>Minimum SF Requirements (with Circulation @ 40%):</b>						<b>823</b>	

E. See Space Criteria Sheets for whiteboard, walk-off mat, and other items required.

LINE NO.	SPEC CODES	RESPONSIBILITY	QTY	DESCRIPTION	SF	Extended SF	REMARKS
<b>Cutter Morro Bay Shop / Storage, Room 120</b>					<b>SF</b>	<b>Extended SF</b>	
38	C2	CFCI	2	Shop Work Stool, casters and ring base	0	0	mobile tool storage units
39	FS1	CFCI	3	Flammable liquids storage cabinets	12	36	
40	R36	CFCI	11	Racks: adjustable shelving	15	165	
41	SS1	CFCI	15	Welded Wire Bulk Storage; locks	15	225	
42	TS2	CFCI	2	5-Dwr Tool Storage Unit, (under workbench)	0	0	
43	TS3	CFCI	2	10-Dwr Tool Storage Unit	27	54	
44	W1	CFCI	1	Tall Waste Basket		0	
45	WB1	CFCI	4	Workbench, hardwood top	27	108	
<b>SUBTOTALS:</b>						<b>588</b>	
<b>Minimum SF Requirements (with Circulation @ 40%):</b>						<b>823</b>	
<b>Cutter Offices (shared), Room 118</b>					<b>SF</b>	<b>Extended SF</b>	
46	C2	CFCI	4	Shop Work Stool, with back, adjustable arms, casters and ring base	0	0	
47	CL1	CFCI	1	Wall Clock			
48	F1	CFCI	4	4-dwr, 36"W lateral files, locking	11	44	
49	RE	CFCI	3	24 gallon recycling containers, Fire Safe Steel	3	9	
50	W1	CFCI	1	Tall Waste Basket			
51	W2	CFCI	4	Metal Waste Basket			
52	WS3	CFCI	4	Touch-down Workstations, approx. 54"W	23	92	
<b>SUBTOTALS:</b>						<b>145</b>	
<b>Minimum SF Requirements (with Circulation @ 31%):</b>						<b>190</b>	
<b>Boat Maintenance Shop, Room 102</b>					<b>SF</b>	<b>Extended SF</b>	
53	C2	CFCI	2	Shop Work Stool, with back, adjustable arms, casters and ring base	0	0	ALMIS computer sits on one of the (4) standard WB's
54	CL1	CFCI	1	Wall Clock		0	
55	FS1	CFCI	1	Flammable liquids storage cabinets	12	12	
56	RE	CFCI	3	24 gallon recycling containers, Fire Safe Steel	3	9	
57	TS1	CFCI	2	Wall Mounted, Tool and Broom racks/holders; rubber coated;	0	0	
58	TS2	CFCI	4	5-Dwr Tool Storage Unit, (under workbench)	0	0	
59	W1	CFCI	1	Tall Waste Basket			
60	WB1	CFCI	4	Workbench, hardwood top	27	108	
61	X1	GFGI	1	ALMIS Tool Computer	25	25	
62	XC2	GFCI	1	Table Vice	1	1	
63	XC5	GFCI	4	Secondary Containment Platforms (metal)	30	120	
64	XC6	GFGI	1	Rolling Tool Cart	11	11	
65	XC7	GFCI	2	Flammable liquids storage cabinets	5	10	
66	XC8	GFCI	1	Grinder; approx. 18"W x 12"D, table mounted	0	0	
67		CFCI	1	First Aid station, wall mounted	0	0	
<b>SUBTOTALS:</b>						<b>296</b>	
<b>Minimum SF Requirements (with Circulation @ 40%):</b>						<b>414</b>	
							<b>Total Does not include Area SF allocation for Boat</b>

E. See Space Criteria Sheets for whiteboard, walk-off mat, and other items required.

LINE NO.	SPEC CODES	RESPONSIBILITY	QTY	DESCRIPTION	SF	Extended SF	REMARKS
<b>MK Shop Parts / ALMIS Tools, Room 106</b>					<b>SF</b>	<b>Extended SF</b>	
68	R36	CFCI	7	Racks: adjustable shelving	14	98	
69	TS4	CFCI	8	10-Dwr Tool Storage Unit	18	144	
70	FS1	CFCI	2	Flammable storage cabinets; for battery Storage	12	24	
71	XC10	GFCI	5	Vidmar Tool Storage			
72	XC11	GFCI	2	2-door storage unit (for ALMIS Tools)	8	16	
<b>SUBTOTALS:</b>						266	
<b>Minimum SF Requirements (with Circulation @ 40%):</b>						372	
<b>General Storage, Room 111</b>					<b>SF</b>	<b>Extended SF</b>	
73	S4	CFCI	4	Wire Shelving, 5-high, seismically secure	14	56	
<b>SUBTOTALS:</b>						56	
<b>Minimum SF Requirements (with Circulation @ 40%):</b>						78	
<b>Janitor Closet, Room 115</b>					<b>SF</b>	<b>Extended SF</b>	
74	E1	CFCI	1	Mop Rack with shelf, wall mounted	0	0	
<b>SUBTOTALS:</b>						0	
<b>Minimum SF Requirements (with Circulation @ 31%):</b>						0	
<b>Recycling/Deliveries, Room 112</b>					<b>SF</b>	<b>Extended SF</b>	
75	RE	CFCI	3	24 gallon recycling containers, Fire Safe Steel	3	9	
76	W1	CFCI	1	Large Waste Receptacle with Lid, minimum 25 gallon	3	3	
<b>SUBTOTALS:</b>						12	
<b>Minimum SF Requirements (with Circulation @ 31%):</b>						16	
<b>SF SUMMARY:</b>							
Sum of SF per Area:						3646	