

SECTION 00 91 11
ADDENDUM NUMBER 1 VE ITEMS

PARTICULARS

- 1.1 DATE: JULY 5, 2011
 - 1.2 PROJECT: ST. MARY'S 12 BED ICF/MR
 - 1.3 PROJECT NUMBER: 1990.10A
 - 1.4 OWNER: ST. MARY'S HOME FOR DISABLED CHILDREN
 - 1.5 ARCHITECT: PF&A DESIGN
- TO: PROSPECTIVE BIDDERS
- 2.1 This Addendum forms a part of the Contract Documents and modifies the revised VE Bidding Documents dated June 23, 2011, with amendments and additions noted below.
 - 2.2 Acknowledge receipt of this Addendum in the space provided in the Supplemental Bid Form for VE Items. Failure to do so may disqualify the Bidder.
 - 2.3 This Addendum consists of 2 Pages:

CLARIFICATIONS

- 3.1 All permits to be handled by the Contractor.

CHANGES TO THE DRAWINGS - STORAGE BUILDING

- 4.1 CIVIL DRAWINGS
 - A. The original Civil bid documents were not revised to reflect the VE Changes. Domestic water and Sanitary line to the Storage building will not be required.
- 4.2 DRAWING A200
 - A. The Room Legend shows the Bathroom. The Bathroom has been removed from the project.
 - B. Detail Section 1 shows a ridge vent for Standing Metal Seam roof. The storage building roof has been changed to an asphalt shingle roof. Please replace and provide Ridge vent for asphalt shingle roof.
- 4.3 DRAWING A400
 - A. Provide Exterior Sign reading: "NO EXPLOSIVE MATERIALS ARE ALLOWED TO BE STORED IN BUILDING". At side of storage building entry door on West elevation.
 - B. South Elevation: A note was left on the elevation for hurricane shutters. Hurricane shutters have been removed from the project.
 - C. North and South Elevations: Provide one Aluminum Vent Louver at 12'-4" A.F.F. to the centerline at each gabled end of building. Paint to match Accent brick. See Specifications.
- 4.4 DRAWINGS A500 and A510
 - A. Provide perimeter insulation under slab, as indicated on structural drawings on sheet S301 – 2" rigid insulation minimum 2' back from exterior foundation wall.
- 4.5 DRAWING A510
 - A. Wall Section 4 shows a cut through a louver. The louver shall match the louvers provided for the ICF/MR home. The louver shall be painted to match the accent brick that frames the louver.

4.6 DRAWING A600

- A. Section Detail 10 shall be deleted from drawings. Bathroom in the Storage Building has been removed from the project.
- B. Finish Schedule: The Bathroom has been removed from the project.

4.7 PLUMBING DRAWINGS

- A. P002: Remove entire sheet from bid set.
- B. P111: Remove entire sheet from bid set.
- C. The foot print on Sheet P110 has not been revised to reflect the VE changes. Please see architectural drawings for building footprint.
- D. The storage building will require a sprinkler system. See Plumbing Drawing Sheet P001.

4.8 DRAWING P110

- A. Room Schedule shows the Bathroom. The Bathroom has been removed from the project.

END OF ADDENDUM NUMBER 1 VE ITEMS