

PROJECT NUMBER: MUHJ 10-4093

PROJECT TITLE: Repair Nor'Easter Damage, Floors/Walls/Ceilings/ Roof, Facility 658

**OFFEROR PLEASE
COMPLETE THE FOLLOWING:**

COMPANY NAME: _____ **DATE:** _____

OFFEROR'S SIGNATURE: _____

TITLE OF PERSON AUTHORIZED TO SIGN: _____

TERMS AND CONDITIONS SPECIFIC TO THIS PROJECT:

NOTICE TO PROCEED: Other than submittal of payment and performance bonds, the Contractor shall not proceed with performance of this project until the Contractor receives a Notice to Proceed from the Contracting Officer.

PERFORMANCE AND PAYMENT BONDS: Payment and Performance Bonds will be required for this project. *Bonds are due no later than 10 calendar days after award.*

WAGE RATES -- The attached Davis Bacon wage decision applicable to this procurement is General Decision Number VA080035, Mod 6, dated 14 August 2009—Building.

LIQUIDATED DAMAGES: In accordance with FAR Clause 52.211-12 the liquidated rate for this project is established at \$463.36.

INVOICES: Invoices may be submitted for progress payments based on a percentage of work completed. Invoices will be submitted electronically using Wide Area Flow (WAWF) procedures.

COMMENCEMENT, PROSECUTION AND COMPLETION OF WORK:

The Contractor shall be required to commence work under this contract within 10 calendar days after the date the Contractor receives the Construction Notice to Proceed, prosecute the work diligently, and complete the entire work ready for use within the stated days after issuance of the Notice to Proceed.

ATTACHMENTS:

Statement of Work
General Decision Wage Determination, VA20080035, Mod 1, dated 16 May 08
Specifications
Floor Plan Bldg 658
AF Form 66

PROJECT NUMBER: MUHJ 10-4093

PROJECT TITLE: Repair Nor'Easter Damage, Floors/Walls/Ceilings/Utilities/Roof, Facility 658

BID SCHEDULE: The following Bid Schedule should be used when submitting prices:

The project involves repairing by replacement of the **windows and associated structure** on the NW and SE sides of the facility -- all seals and gaskets on and around the windows are to be removed and replaced and the color and finish of the new materials shall match the existing. / Repair by replacement the **carpet and door and window seals in the U room (see attached drawing)** -- the new carpet texture, grade, finish and appearance shall match that of the non-damaged rooms. The color and finish of the new materials on the doors and windows shall match the existing. / Repair by replacement the **ceiling patches over the gym floor** that leak -- includes the repair of areas of roof and ceiling that leak into the building (approx. 500SF). The contractor shall determine the cause and source of the leaking through field investigation and make appropriate repairs. The color and finish of the ceiling shall match existing area. This repair shall be completed before work begins on installing the new gym floor. / Repair by replacement the **gym floor**. -- includes the replacement of the hardwood floor system and related appurtenances. The floor must meet the DIN floor standards outlined by the American College of Sports Medicine (ACSM) which are: Shock Absorption- 53% minimum; Standard vertical deformation- 2.3mm; Minimum Deflective Indentation- 15%; Maximum Sliding Characteristics- 0.5 to 0.7 range; Ball Deflection- 90% minium; Rolling Load -- 337.6 lb. Additionally, the floor will not be wood and must be able to withstand being submerged for a prolonged period under saltwater from the Back River without being damaged. The contractor shall ensure that the Sub-Contractor used to install the new floor is a reputable business, having five years or more experience in installing synthetic gym floors. The contractor shall provide the Government examples of at least four (4) projects that are within the same price range that were accomplished within the last three (3) years, as well as POC's and contact information. / Repair by replacement **ceiling over cardio area** -- the ceiling over the upper cardio area leaks and has made a hole in the ceiling. The Contractor shall determine the cause and source of the leaking through the field investigation and make appropriate repairs. The color and finish of the ceiling repair shall match the existing area. **This is a bid/build project.**

1 JOB \$ _____

Please Note: Upon submitting the cost proposal, an AF Form 3052 is required for this project in accordance with the General Provisions of the contract.