

BIDDING SCHEDULE

**MUHJ 08-7027A, CONSTRUCT/INSTALL ELECTRIC SIGNAGE, AIRFIELD,
633 CES**

LANGLEY AFB, VIRGINIA

<u>BID ITEM NO.</u>	<u>DESCRIPTION</u>	<u>LUMP SUM</u>
0001	Mobilization/Demobilization: All work, equipment, storage and transport of materials and personnel, utility connections and billing, temporary Contractor facilities, security fencing, and the restoration of staging and stockpile areas required for Contractor activity for the duration and completion of the project as called out in the plans and specifications and to the satisfaction of the Contracting Officer. 1 LS.	\$ _____
0002	Temporary Construction Items: All temporary signage, flaggers, guardsmen, barricades, construction fence, silt fence (for stockpile), construction entrance(s), temporary seeding, dust control, sweeping, temporary drainage, and communications as called for in the plans and specifications and as required by the Contracting Officer to meet Local and State regulations for Erosion and Sediment Control, Stormwater Management, and Airfield Operations Area Safety. 1 LS.	\$ _____
0003	Underground Cable, No. 8-AWG, 5 kV, L-824, Type B: All cable to be installed in either sand encased or concrete encased duct bank including all necessary splicing, tagging, and other incidentals required to power new signage through existing circuits as called for in the plans and specifications. 5,322 LF.	\$ _____
0004	Underground Cable, No. 4-AWG, Bare Counterpoise: All bare counterpoise to be installed in either sand encased or concrete encased duct bank trenches including all connections and ground rods required to complete the counterpoise system as called for in the plans and specifications. 2,575 LF.	\$ _____
0005	1Way-2 Inch PVC Conduit, Sand Encased: All excavation, backfill, compaction, topsoiling, seeding and mulching, installation of detectable	

marking tape, installation of new stub outs into existing cans, and PVC conduit and fittings to be installed as called for in the plans and specifications. 2,378 LF.

\$ _____

0006

1Way-2 Inch PVC Conduit, Concrete Encased: All excavation, backfill, compaction, topsoiling, seeding and mulching, installation of detectable marking tape, installation of new stub outs into existing cans, concrete, pavement, pavement marking, and PVC conduit and fittings to be installed as called for in the plans and specifications. 140 LF.

\$ _____

0007

LED Lighted Mandatory Hold Sign: All equipment, labor, and materials for the complete installation of signage foundation and sign, including but not limited to: excavation, backfill, compaction, final grading, topsoiling, seeding and mulching, formwork, steel reinforcement, structural concrete, L-867 base can and cover, isolation transformers, wiring, L-824 cable connectors, conduit and fittings, stub outs, ground wiring, ground rod, and bird perch inhibitors and all other necessary incidentals as shown in the plans and specifications per sign regardless of the number of modules. 2 EA.

\$ _____

0008

LED Lighted Guidance Sign: All equipment, labor, and materials for the complete installation of signage foundation and sign, including but not limited to: excavation, backfill, compaction, final grading, topsoiling, seeding and mulching, formwork, steel reinforcement, structural concrete, L-867 base can and cover, isolation transformers, wiring, L-824 cable connectors, conduit and fittings, stub outs, ground wiring, ground rod, and bird perch inhibitors and all other necessary incidentals as shown in the plans and specifications per sign regardless of the number of modules. 33 EA.

\$ _____

Aggregate of Bid Line Items 0001 thru 0008.

\$ _____

BIDDING SCHEDULE

MUHJ 08-7027B, REPAIR/INSTALL ELECTRIC SIGNAGE, AIRFIELD, 633 CES

LANGLEY AFB, VIRGINIA

<u>BID ITEM NO.</u>	<u>DESCRIPTION</u>	<u>LUMP SUM</u>
0001	Mobilization/Demobilization: All work, equipment, storage and transport of materials and personnel, utility connections and billing, temporary Contractor facilities, security fencing, and the restoration of staging and stockpile areas required for Contractor activity for the duration and completion of the project as called out in the plans and specifications and to the satisfaction of the Contracting Officer. 1 LS.	\$ _____
0002	Temporary Construction Items: All temporary signage, flaggers, guardsmen, barricades, construction fence, silt fence (for stockpile), construction entrance(s), temporary seeding, dust control, sweeping, temporary drainage, and communications as called for in the plans and specifications and as required by the Contracting Officer to meet Local and State regulations for Erosion and Sediment Control, Stormwater Management, and Airfield Operations Area Safety. 1 LS.	\$ _____
0003	Underground Cable, No. 8-AWG, 5 kV, L-824, Type B: All cable to be installed in either sand encased or concrete encased duct bank including all necessary splicing, tagging, and other incidentals required to power new signage through existing circuits as called for in the plans and specifications. 14,758 LF.	\$ _____
0004	Underground Cable, No. 4-AWG, Bare Counterpoise: All bare counterpoise to be installed in either sand encased or concrete encased duct bank trenches including all connections and ground rods required to complete the counterpoise system as called for in the plans and specifications. 7,141 LF.	\$ _____
0005	1Way-2 Inch PVC Conduit, Sand Encased: All excavation, backfill, compaction, topsoiling, seeding and mulching, installation of detectable marking tape, installation of new stub outs into existing cans, and PVC	

conduit and fittings to be installed as called for in the plans and specifications. 7,122 LF.

\$ _____

0006

1Way-2 Inch PVC Conduit, Concrete Encased: All excavation, backfill, compaction, topsoiling, seeding and mulching, installation of detectable marking tape, installation of new stub outs into existing cans, concrete, pavement, pavement marking, and PVC conduit and fittings to be installed as called for in the plans and specifications. 140 LF.

\$ _____

0007

LED Lighted Mandatory Hold Sign: All equipment, labor, and materials for the complete installation of signage foundation and sign, including but not limited to: excavation, backfill, compaction, final grading, topsoiling, seeding and mulching, formwork, steel reinforcement, structural concrete, L-867 base can and cover, isolation transformers, wiring, L-824 cable connectors, conduit and fittings, stub outs, ground wiring, ground rod, and bird perch inhibitors and all other necessary incidentals as shown in the plans and specifications per sign regardless of the number of modules. 19 EA.

\$ _____

0009

Remove Lighted Airfield Sign: All equipment, labor, and materials for the deactivation of existing signage, demolition of existing signage foundations, disposal, backfill, final grading, topsoiling, seeding, and mulching as called for in the plans and specifications and directed by the Contracting Officer. Note that existing signs and isolation transformers are to be salvaged and returned to the 633 CES. 19 EA.

\$ _____

0010

Remove L-861T Edge Light and Base: All equipment, labor, and materials for the temporary deactivation of existing edge light and base can, disposal, backfill, final grading, topsoiling, seeding, and mulching as called for in the plans and specifications. Note that edge light and isolation transformer are to be salvaged and reused. 3 EA.

\$ _____

0011

L-867 Base Can with Existing Light: All equipment, labor, and materials for the installation of concrete encased base can, stub outs, existing isolation transformer, existing edge light, backfill, final grading, topsoiling, seeding, and mulching. 3 EA.

\$ _____

Aggregate of Bid Line Items 0001 thru 0011.

\$ _____