

REQUEST FOR PROPOSAL (RFP)
Langley AFB Multiple Award Construction Contract (MACC)
Amendment 02

Issued By: 633d Contracting Squadron/LGCB
74 Nealy Avenue
Langley AFB, VA 23665

September 20, 2010

Point of Contact: Michael Costlow, 764-2597 or Samuel W. Brown, 225-5256

PROJECT NUMBER: MUHJ 10-4108

PROJECT TITLE: Repair Bethel Reservoir Fence

Subject RFP is amended to incorporate clarification to the below RFI questions.

1. Paragraph 1.3.1 of the SOW states to repair depressions, recesses and eroded areas of earthwork. What is the allowable distance between the bottom of the fence and the ground?
(1) Inch clearance between the bottom of the fence fabric and the finish grade is allowed.
2. In paragraph 1.3.5 of the SOW and stated in the meeting: That what material is removed must be put back the same day. This is not feasible due to the clearing, demolition, fence post installation (concrete must have time to cure) and fabric installation. Suggest that there be a limit of removal and placement, for example no more than 500 to 750 lf can be removed at any time.
Because of the potential liability involved in leaving a fence section out, Legal guidance mandates the requirements found in SOW item 1.3.5.
3. Will it be allowable to have the cleared vegetation left on site in the wooded areas to be used as natural mulch?
Existing vegetation (i.e., fallen trees) can be cleared and left in the woods as natural mulch. Trees and limbs, cut as a result of this project, need to be chipped before being left in the wooded areas. In all cases, vegetation being left needs to be blended in to the environment and not left as big stacks of debris.
4. Will it be acceptable to have the existing fence post that are to be remove to be cut off flush to top of concrete footer and the concrete left in place?
No, the poles and concrete need to be removed and disposed of properly.