


**BATHROOM LAYOUT**

SCALE: 1/4" = 1'-0"



**1. Men's Room**

- 1.1. Install (2ea) two piece elongated floor mounted toilet with open front seat. The elongated combination shall have a 12" rough in, 1.6 GPF, vitreous china, elongated front rim, 2 inch fully glazed trap way. Shall be equivalent to or better than Kohler Model K-3589 1.6 GPF Elongated floor mounted toilet.
- 1.1.1. Install (2) new stall bathroom stall partitions and (1) urinal partition. Bathroom partitions shall be made of solid plastic polymer units made from high density polyethylene plastic. To include all hardware and doors.
- 1.1.2. Install (2ea) standard 2 roll bath tissue dispensers; Chrome plated 2 roll surface mounted with concealed push-button hinge release.
- 1.2. Install (2ea) commercial wash out urinals with 1.5 GPF. Urinal shall be wall hung mounting style, connection top spud 3/4" Vitreous China material. Urinals shall be equal to Zurn model #Z5798.205.00. Urinals shall have a commercial type flush valve equal to Zurn model # Z6003AV-WS1 lever handle.
- 1.3. Install (3ea) Wall mounted hands free sinks. Sinks shall be 18gauge stainless steel with welded 9 1/2" backsplash. Knee operated double pedal valves, with swivel gooseneck spout. To include soap dispenser.
- 1.3.1. Overall dimensions; length 19-inches; width 18-inches; height 14-inches.
- 1.3.2. Sink shall be similar to SANI-LAV hand free sink model# 1HLF3.
- 1.3.3. Conceal all piping behind wall.
- 1.3.4. Install new angle stops, supply lines, "P" traps and any miscellaneous parts.
- 1.3.5. Install (3ea) 18-inches x 24-inches wall mounted mirror with 5-inch shelf. Mount above sinks.
- 1.4. Clean tile in shower area and seal.
- 1.4.1. Restore ceramic shower stall wall and ceramic shower stall floor using a restoration system equal to the SaniGlaze system. The restoration system shall:
  - 1.4.1.1. Extract contaminants (soil, grease, sealer, finish, mold) from the grout and tile surfaces.
  - 1.4.1.2. Apply permeating renewal glazing compound to grout lines. This shall become a permanent part of the grout line.
  - 1.4.1.3. Apply shield to the tile and grout surfaces.
- 1.5. Install (2) new shower curtains and rods.
- 1.6. Replace existing towel hooks in shower area.
- 1.7. Replace missing shower head with handheld showerhead.

**SPECIAL SCHEDULING AND ACCESS:**

1. Access and scheduling to the work area shall be arranged through Contracting Officer's Representative for the OICC office, and Mr. Matthew Brinkley, the tenant of the building. Mr. David Lynch, (910) 451-9563 or (910) 376-5082.

**HAZARDOUS MATERIALS:** None Identified. Tested 12/10/1999 for asbestos and found to contain no asbestos materials in work area.

**SPECIAL CONDITIONS:** None Identified

**ENVIRONMENTAL REQUIREMENTS:** None Identified

BLDG# 1700	SHEET 6 OF 7
CONTRACT# N40085-09B-0513	
DWG. DAVID BELEDNARD	MACC# 09-0513
PARTIAL RENOVATION	
USMC CAMP LEBJUNE	
A5	